BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to : **Original / Duplicate**

NAME OF THE WORK:-Improvements to drains of 11st to 14th cross roads of jakkur layout in ward No.07, Byatarayanapura.

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	486.81	KSRRB 300-1. Earthwork excavation by manual means in rodinary soil involving an average horizontal throw upto 2 m and an average lift upto 1.5m, excavated surafce levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking clods complete as per specifications.. Pg No.141.Item No.19.1)	cum	86.92	Rupees Eighty Six and Ninety Two Paise Only
2	95.83	KSRB 4-1.3: Providing and laying in position plain cement concrete of nominal mix 1:4:8 using 40mm and down size graded granite metal machine mixed, conrete laid in layers not exceeding 15 cms. Thick well compacted in foundation and plinth, including cost of all materials labour, HOM of machinery, curing complete as per specification . (Pg.No.12, It.4.3)	cum	5159.02	Rupees Five Thousand One Hundred Fifty Nine and Two Paise Only
3	205.88	KSRB 4.2.2: Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320 Kgs with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum with superplastizers @ 3lts confirming to IS 9103-1999 RE affirmed - 2008 machine mixed, concrete laid in layers not exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, stair case lintels, retaining walls return walls, walls(anythickness) including attached plasters columns piers abutments pillars posts struts butresses string or lacing courses parapets copings, bed blocks , plain windows cills fillets etc., including cost of all materials labour HOM of machinery curing complete as per specifications. Seocifications No. KBS 4.1,4.6 (Page NO. 13, Item NO. 4.11)	cum	6371.66	Rupees Six Thousand Three Hundred Seventy One and Sixty Six Paise Only
4	11.32	Providing TMT Steel Reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.(Page No.17, Item No.17)	Tonne	64243.42	Rupees Sixty Four Thousand Two Hundred Forty Three and Forty Two Paise Only
5	1704.00	Providing and removing Centering, shuttering, strutting, propping etc., for columns, pillars, piers, abutments, post and struts, square / rectangular slabs /side walls polygon in plan including cost of materials, labour complete as per specification and directions of the Engineer in charge.(Page No.16, Item NO.4.32)	Sqm	387.96	Rupees Three Hundred Eighty Seven and Ninety Six Paise Only
6	15.75	KSRB4-1.6: Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240 kgs, with 20 mm and down size graded granite matel coarse aggregates @ 0.69 cum and fine aggragtes @ 0.459cum, machine mixed concrete laid in layers not eceeding 15 cms, thick well compacted, in foundation, plinth and cills including cost of all materials, labour HOM machinery curing complate as per specifications. (Page No. 12. Item No. 4.6)	cum	5767.46	Rupees Five Thousand Seven Hundred Sixty Seven and Forty Six Paise Only
7	532.50	Providing and fixing 10cms thick pre cast RCC covering slab using reinforced cement concrete M20 mix with stone aggregate 20mm and down size including centring shuttering reinforcement and bar bending machine mixed concrette laid in layers not exceeding 15 cm thick wellcompacted cost of all materials labour curing complete as per specfications (Data Rate Approved)	cum	2100.00	Rupees Two Thousand One Hundred Only
8	38.00	Providing and fixing MS Grating 260x260 mm(Page No.VIII, Sl No.237, code No.0771)	Nos	94.34	Rupees Ninety Four and Thirty Four Paise Only

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
9	486.81	KSRRB M100-1 Loading and unloading of stone boulder/stone aggregates/ sand/ kanker/ moorum. KSRRB M100-1:Placing tipper at loading point loading with front end loading, dumping turning for return trip, excluding time for haulage and return trip complete as per specification MORTH Chapter 1 (Page 118, item No. 17.1)	cum	106.00	Rupees One Hundred Six Only

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

28/12

Note:

1. Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of quantities (refer: ITB Clause 7.2 and CC Clause 33.2)
2. Unit rates and prices shall be quoted by the Tender in Indian rupees.
3. Where there is a discrepancy between the rate in figures and words the rates in words will govern (ITB Clause 19.1(a)
4. Where there is a discrepancy between the unit rate and the line item total resulting from multyplying the unit rate by quantity the unit rate quoted shall govern (ITB Clause 19.1(b))

"DTS Approved"

Chief Engineer
Yelahanka Zone
12.1.18
Bbath Bangalore Mahanagara
Rangalore 92